


PLACE ARROW INDICATING NORTH DIRECTION RELATIVE TO CROSSING

FORM DR-0404-B  
REV. 5-15-98

# ENCASED NON-FLAMMABLE PIPELINE CROSSING

NOTE: ALL AVAILABLE DIMENSIONS MUST BE FILLED IN TO PROCESS THIS APPLICATION.

NO SCALE



MINIMUM THICKNESS	DIAMETER OF CASING PIPE
.2500"	1/4" 12" OR LESS
.3125"	5/16" OVER 12"-18"
.3750"	3/8" OVER 18"-22"
.4375"	7/16" OVER 22"-28"
.5000"	1/2" OVER 28"-34"
.5625"	9/16" OVER 34"-42"
.6250"	5/8" OVER 42"-48"

OVER 48" MUST BE APPROVED BY R.R. CO.  
NOTE: THIS CHART IS ONLY FOR SMOOTH STEEL CASING PIPES WITH MINIMUM YIELD STRENGTH OF 35,000 PSI.

FORMULA TO FIGURE CASING LENGTH WITH ANGLE OF CROSSING OTHER THAN 90°

$$\frac{B}{\sin \Delta} = \text{1/2 CASING LENGTH}$$

B MIN. DIST. (NOTE 2)

- NOTES :
- 1) ALL HORIZONTAL DISTANCES TO BE MEASURED AT RIGHT ANGLES FROM  $\phi$  OF TRACK.
  - 2) CASING TO EXTEND BEYOND THE  $\phi$  OF TRACK AT RIGHT ANGLES THE GREATER OF  $2D + 20$  FT., OR 30 FT., AND BEYOND LIMIT OF RAILROAD RIGHT-OF-WAY IF NECESSARY TO PROVIDE PROPER LENGTH OUTSIDE OF TRACK.
  - 3) MINIMUM OF 50' FROM THE END OF ANY RAILROAD BRIDGE,  $\phi$  OF ANY CULVERT, OR FROM ANY SWITCHING AREA.
  - 4) SIGNAL REPRESENTATIVE MUST BE PRESENT DURING INSTALLATION IF RAILROAD SIGNALS ARE IN THE VICINITY OF CROSSING.
  - 5) ALLOWABLE FIXED OBJECTS INCLUDE: BACKWALLS OF BRIDGES;  $\phi$  OF ROAD CROSSINGS & OVERHEAD VIADUCTS (GIVE ROAD NAME), OR CULVERTS.
  - 6) CASING AND CARRIER PIPE MUST BE PLACED A MINIMUM OF 2 FEET BELOW THE EXISTING FIBER OPTIC CABLE. ANY EXCAVATION REQUIRED WITHIN 5 FEET OF THE EXISTING FIBER OPTIC CABLE MUST BE HAND DUG.

A) IS PIPELINE CROSSING WITHIN DEDICATED STREET? YES; NO;

B) IF YES, NAME OF STREET \_\_\_\_\_

D) DISTRIBUTION LINE \_\_\_\_\_ OR TRANSMISSION LINE \_\_\_\_\_

C) CARRIER PIPE :  
COMMODITY TO BE CONVEYED \_\_\_\_\_  
OPERATING PRESSURE \_\_\_\_\_ PSI  
WALL THICKNESS \_\_\_\_\_; DIAMETER \_\_\_\_\_; MATERIAL \_\_\_\_\_

E) CASING PIPE :  
WALL THICKNESS \_\_\_\_\_; DIAMETER \_\_\_\_\_; MATERIAL \_\_\_\_\_  
NOTE : CASING MUST HAVE 2" CLEARANCE BETWEEN GREATEST OUTSIDE DIAMETER OF CARRIER PIPE AND INTERIOR DIAMETER OF CASING PIPE. WHEN FURNISHING DIMENSIONS, GIVE OUTSIDE OF CARRIER PIPE AND INSIDE OF CASING PIPE.

F) METHOD OF INSTALLING CASING PIPE UNDER TRACK(S) :  
\_\_\_\_\_ DRY BORE AND JACK (WET BORE NOT PERMITTED) ;  
\_\_\_\_\_ TUNNEL ; OTHER \_\_\_\_\_

G) WILL CONSTRUCTION BE BY AN OUTSIDE CONTRACTOR? YES; NO;

H) DISTANCE FROM CENTER LINE OF TRACK TO NEAR FACE OF BORING AND JACKING PITS WHEN MEASURED AT RIGHT ANGLES TO TRACK \_\_\_\_\_ (30' MIN.)

I) APPLICANT HAS CONTACTED 1-800-336-9193, U. P. COMMUNICATION DEPARTMENT, AND HAS DETERMINED FIBER OPTIC CABLE \_\_\_\_\_ DOES ; \_\_\_\_\_ DOES NOT ; EXIST IN VICINITY OF WORK TO BE PERFORMED. TICKET NO. \_\_\_\_\_

**EXHIBIT "A"**  
(FOR RAILROAD USE ONLY)

(SUBDIVISION) \_\_\_\_\_

M. P. \_\_\_\_\_ E. S. \_\_\_\_\_

ENCASED \_\_\_\_\_ CROSSING AT \_\_\_\_\_

(NEAREST CITY) (COUNTY) (STATE)

(APPLICANT) \_\_\_\_\_

RR FILE NO. \_\_\_\_\_ DATE \_\_\_\_\_

**WARNING**

IN ALL OCCASIONS, U. P. COMMUNICATIONS DEPARTMENT MUST BE CONTACTED IN ADVANCE OF ANY WORK TO DETERMINE EXISTENCE AND LOCATION OF FIBER OPTIC CABLE.  
PHONE : 1-800-336-9193